



Accelerator Operations and Strategies

R. Dixon



Overview

- Tevatron Collider Highlights
 - Performance over the past year
 - Plans for improvements and strategies
 - Luminosity models and projections
- Neutrino Performance
 - Performance in 2006/2007
 - The path to future neutrino beams
- Test Beam



Accelerator Operations Overview


- Collider Run 2
 - Tevatron proton-antiproton collisions to CDF and D0
 - Design goal = 8 fb^{-1} by end FY09
 - Delivered $> 2.8 \text{ fb}^{-1}$ so far
 - Integrated luminosity has made dramatic increases during the past year

- Neutrino Program
 - MiniBooNE: 8 GeV protons from Booster
 - 8.9 E20 protons-on-target (neutrino/antineutrino modes combined)
 - NuMI: 120 GeV protons from Main Injector (MI)
 - 3.29 E20 protons-on-target
 - Proton Plan & beyond: increase proton beam power

- Switchyard 120 – Meson Test Beam Facility (MTBF)
 - Deliver 120 GeV protons and 1-64 GeV secondaries π , K, p, e, μ
 - Run in parallel with Run 2 and neutrino program
 - 1 slow/fast spill from MI every 60 seconds $\sim 12 \text{ hr/day}$





Total Run II Luminosity






Run II Delivered Luminosity June 06 to June 07






Integrated Luminosity for January 2007

Delivered Luminosity: Jan-01-2007 to Feb-01-2007 167.171 (1/pb)





Records

- Comparing before and after 2006 shutdown data
 - Peak Luminosity increased by 62% (180 E30 --> 292 E30)
 - Weekly integrated Luminosity Record increased by ~ 75% (25 pb⁻¹ --> 45 pb⁻¹)
 - Monthly integrated luminosity increased by ~ 95% (85 pb⁻¹ --> 167 pb⁻¹)
 - Numerous peak luminosity records were set during this period
 - One hour stacking record-- 23.1 ma/hr
 - Antiproton accumulation for one week-- 2800 E10



Tevatron Highlights

- Reliability
 - Replaced all ≈ 1200 LHe Kautzky valves (cause of 2 FY06 dipole failures)
 - Modifying quench protection system to allow faster beam aborts
 - Cog antiprotons out of abort gap for acceleration to prevent needless quenches


- More antiprotons with smaller emittances to HEP
 - Increased stacking rate in Antiproton Source
 - New working point in Recycler
 - Better antiproton lifetime @ 150 GeV from new helical orbit, reduced beam-beam

- Injecting $\approx 10\%$ more protons


- Improved luminosity lifetime
 - Additional separators increase separation (20% at nearest parasitic crossings upstream of interaction points)
 - Beam-beam effects reduced - performance agrees better with model neglecting beam-beam



Comparing to Model without Beam-Beam Effects



Before shutdown (Jan. 6, 06)



After shutdown (July. 27, 06)

V. Lebedev

- After shutdown, luminosity evolution for similar stores agrees better to model without beam-beam effects
- Most pbars lost during HEP are burned in luminosity (good!)
- Protons suffering from head-on beam-beam due to brighter pbars
 - Limited tune space



Tevatron Plan

- Implement 2nd order chromaticity correction @ low β
 - Installed and being commissioned
 - Will allow pursuit of a new working point
- Pursue other minor improvements (few % each)
 - Scrape (higher intensity) protons @ 150 GeV
 - Investigating new cogging between pbar injections
 - Reduce beam-beam effects by changing locations of long-range crossings
 - Use TELs (electron lenses) on protons for beam-beam compensation
 - Raise tunes of individual bunches away from 7/12 resonance to improve lifetime
 - More reliable (bunch-by-bunch) tune measurements
 - Better helices, improved transfer line matching, faster shot-setups, etc.




Antiproton Improvements

- Antiprotons delivered to Tevatron increased by 45%
 - Accumulator stacktail gain correction - 12%
 - Fast Accumulator-to-Recycler transfers - 10%
 - Recycler to Tevatron transfer efficiency - 6%
 - Misc. (reliability, etc.) - 11%
- Other factors
 - Lithium lens -- increasing gradient
 - Focus more pbars into AP2 line leading to Debuncher/Accumulator
 - Developed Model to understand stacktail -- good match to data (Lebedev)
 - Stacktail cooling in Accumulator identified as major bottleneck
 - New Recycler working point
 - Reduce impact of space charge tune shift; smaller emittances
 - Pbar bunch intensity leveling in Recycler
 - Uses RF feed-forward system to reduce bunch-to-bunch variations
 - Helpful for Tevatron and experiments' trigger/DAQ systems





Antiproton Stacking Improvements

- Major items
 - New Stacktail Gain Equalizers
 - First installed in March
 - Second installed on past Monday
 - New Accumulator Lattice
 - Installed in May
- Other Items
 - Implementation of leg 3 stochastic cooling-- done
 - Improve Debuncher cooling-- in progress
 - Improve Debuncher and Accumulator orbits and matching optics-- in progress
- Misc
 - Re-install new style lithium lens with higher gradient
 - Improves flux into Debuncher
 - Two recent failures




Run II Weekly Antiproton Accumulation







Reducing Time for Pbar Transfers to Recycler





Best Stacking Hour in a Day






Present Collider Plan

- Increase pbar stacking rate
 - Change Accumulator Lattice to optimize stacktail-- done
 - Install second new equalizer for stacktail gain-- done
 - Tune stacking with improvements
 - Put new style lithium lens back in asap
- Slowly increase stash size in the Recycler
- Implement 2nd order chromaticity correction in Tevatron to improve lifetimes (New sextupole circuits)
- Optimize peak vs. integrated luminosity with experiments
 - Approaching design 320 pb⁻¹/s peak luminosity
- Continue to work on reliability in all machines
- Investigate new strategies



2006 Projection Curves






Parameters for Projections

- Number of protons per bunch
- Luminosity Density @ 100×10^{10}
- Luminosity Density @ 300×10^{10}
- Init Tevatron Lifetime @ $80 \mu\text{b}^{-1}/\text{sec}$
- Init Tevatron Lifetime @ $160 \mu\text{b}^{-1}/\text{sec}$
- HEP store hours per week
- Acc-Rec Transfer Efficiency @ 0×10^{10}
- Acc-Rec Transfer Efficiency @ 300×10^{10}
- Acc-Rec transfer time
- Recycler mining efficiency
- Recycler lifetime
- Initial Stacking Rate
- Half rate stack size
- Maximum stack size
- Timeline Utilization Factor
- Accumulator leftover factor

The output (initial, integrated lum.) depends on the average store length and the number of antiproton transfer shots between stores.




Projected Luminosity from Model





All Projection Curves





Maximizing Investments

- Strategy Group

- Charge


- Maximize final integrated luminosity delivered to experiments
 - Investigate ongoing improvements to determine payoff
 - Explore new strategies with potential to increase luminosity
 - Continue the Development and use of models to make cost/benefit determinations




Neutrino Program


- MiniBooNE
 - Booster improvements during shutdown allowing higher throughput - exceeding design proton delivery rate
 - Resumed run after 14 week shutdown for absorber repairs

- NuMI
 - FY07 already best year: >1.2 E20 POT delivered
 - Improvements in slip-stacking
 - 2+5 mode operational
 - 180-200 kW beam power with pbar production
 - 250-300 kW running NuMI-only
 - 2+9 mode being developed for FY08 running
 - Single pulse record > 4 E13
 - Want to push pbar production cycle 2.4 _ 2.2 sec
 - Already @ 2.2 sec during pbar shots to Recycler




MiniBooNE Protons in FY07






Protons Delivered to NuMI






FY07 NuMI Delivered Protons





Slipping Stacking

- The Main Injector has six usable "slots", into which Booster batches may be placed.
- More batches may be loaded, using "slip stacking", in which an initial batch in the Main Injector is accelerated such that a subsequent batch will be at a slightly different energy.
- The two will then drift together and can be captured as a single batch (with at least twice the longitudinal emittance).





Slip Stacking in the Main Injector

- Space for 6 Booster batches + 1 empty slot

$$\begin{array}{cccccc} \bar{P} & N & N & N & N & N & _ \\ \hline & & & & & & \end{array} \quad (1+5)$$

- Slip stacking allows (present operating scenario)

$$\begin{array}{cccccc} & \bar{P} & & & & & \\ \bar{P} & N & N & N & N & N & _ \\ \hline & & & & & & \end{array} \quad (2+5)$$

- Recent Successes in slip stacking lead to this possibility

$$\begin{array}{cccccc} & \bar{P} & & & & & \\ \bar{P} & \begin{array}{c} N \\ N \end{array} & N & _ \\ \hline & & & & & & \end{array} \quad (2+9)$$



NuMI Plan

- Slip Stacking Success has position us to implement (2+9) batch operation for NuMI
 - Presently running (2+5) mode
 - Conduct Studies on (2+9)-- In progress
 - Install collimators in Main Injector-- summer shutdown
 - Commission (2+9) batch operation after shutdown (up to 400KW)
 - Complete Proton Plan and Accelerator NuMI Upgrades (ANU)



Staged Neutrino Program

- Proton Plan
 - MI RF improvements and operational loading initiatives increase NuMI intensity to 4-5 $\times 10^{13}$ protons per 2.2 second cycle ($\approx 3 \times 10^{20}$ protons/yr)
 - Ultimately 320 kW to NuMI (400 kW when not running pbar source)
 - Runs through end of collider program
 - ANU ("Accelerator NuMI Upgrades", combined with NOvA as per DOE)
 - Use Recycler as pre-loader to save time injecting into MI
 - ~700 kW to NOvA
 - Presently being formalized and baselined
 - Future Possibilities
 - SNuMI (formerly "SNuMI II")
 - Momentum-stack protons in Accumulator _ boxcar stacking in Recycler
 - Ultimately ~1.2 MW to NuMI
 - Still in early conceptual stage
 - HINS (formerly "Proton Driver")
 - New 8 GeV proton linac to Main Injector, exploit synergy with ILC
 - ≥ 2 MW to NuMI
 - Not part of our official planning at this point
-



Summary

- Significant Run II progress in the past year
 - Stacking Rate improvements continue
 - Developing Strategy to maximize integrated Luminosity
- NuMI and MiniBooNE have run well over the past year
- Improvements will continue for the neutrino beam
 - Slip stacking for (2+9) scenario
 - Completion of Proton Plan
 - Execution of ANU
 - Possible future upgrades